

OFFICE OF THE MARION COUNTY SURVEYOR

SECTION RECORD CORNER

SECTION 10 TOWNSHIP 16 RANGE 4

DATE: 8-16-06

PARTY CHIEF: Wilcoxen

CREW: _____

TYPE OF MARKER: Raised Harrison


METHOD OF ESTABLISHMENT: County: 2-11-99

IN... S.P.C. E ZONE NAD '83

NAME: 16041001

N: 511516.9540(m)

E: 64285.4300(m)



Original post set 1820 by Hendricks with witness: 8" hickory S 67 W 18 links; 30" white oak S 88 E 26 links per Washington Township Legal Survey Book pg. 21. Survey, 1850, by Hosbrook called corner 'B' giving witness: 14" walnut S 78 1/4 E 97 1/3 links; 2" locust N 37 W 53 1/2 links. Legal Survey 11-1866 by Smith per Lawrence Township Legal Survey Book pg. 18 called corner 'I' and called a stone. Legal Survey 10-1898 by Coyner per Washington Twp. Legal Bk, pg. 25 called corner stone with distances to corners on the S & W. Survey (undated) per Lawrence Twp Legal Bk pg. 68 called stone. Washington Twp. Legal Bk pg.146 by Wilkerson 11-1946 called distance to the corner from the C/L of Millersville Rd. Undated, tie card called distance across N line agree with distance noted in 1946 Legal Survey.(2) additional, undated cards called corner but no ties or info given. 7-20-51 Monroe called nail voer stone. 5-18-70 McLand called PK nail and agreed with earlier ties. Corner destroyed 19-80-1981 w/construction. Reestablished by MCS 1981. Agreed within 0.1'. Harrison set. Re-tied every five years.

16041001

REF.	DISTANCE	DESCRIPTION
1.	41.26'	Cut 'x' S-rim traffic manhole
2.	64.43'	Cut 'x' SF-bolt of signal pole base
3.	89.91'	Cut 'x' W-rim of traffic manhole in median
4.	34.98'	Cut 'x' E-rim of traffic manhole (E-of sewer manhole)
5.	52.05'	Cut 'x' SF bolt of signal base
6.	47.60'	Road nail NE PwP#24-343A 10"up